MYSORE DIVISION.

Notice dated 15th October 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 5th November 1927, for Restoring Halepur Tank, Nanjangud Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M., on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the from given below, showing the rates at which the different items specified will be executed as clearly stated at what percentage less than the estimated amount the works will be carried out :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees five hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Halepur Tank, Nanjangud Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for Restoring Halepur Tank, Register No. 26, Nanjangud Taluk Mysore District :—

No.	Items of work	Per	Rate	Quantity	Cost
	I. BUND.		Rs. a. p.		Rs.
1	Jungle clearing	Grade	3 0 0	38	114
2	Cutting grips to bund	,,	2 0 0	35	70
3	Excavating soft stuff and white stony soil ...	Grades	1 0 0	1233	1,233
4	Split rough stone in surki mortar ...	C.ft.	0 6 0	3944	1,479
5	Earthwork to bund with consolidation including lead and lift, complete.	Grades	0 5 0	11560	3,612
6	Excavating, carting, spreading and consolidating gravel.	,,	0 12 0	1,800	1,350
7	New stone revetment with 5 miles lead ...	,,	3 0 0	1343	4,029
8	Removing and refixing grade stone including cutting figures and painting.	Each	0 12 0	41	31
9	Removing and refixing top width stones ...	,,	0 4 0	38	10
10	Providing and fixing top width stone in place of missing.	,,	1 0 0	3	3
11	Providing and fixing B. M. stones including cutting figures and painting.	,,	5 0 0	2	10
12	Providing and fixing Reg. No. and date stones including cutting letters and painting.	,,	5 0 0	2	10
13	Providing and fixing gauge stones ...	Lump sum rupees			50
14	Baling water	Lump sum rupees			50
15	Unforeseen items	Lump sum rupees			21
	Total for bund ...	...	...	...	12,072

No.	Item of work	Per	Rate	Quantity	Cost
	II. REPAIRING SLUICE No. 1.		Rs. a. p.		Rs.
1	Constructing the damaged front and rear cisterns, etc.	Lump sum	rupees		200
	III. LEFT WEIR 322 FEET LONG AT R. L. 50·00.				
1	Jungle clearing	Lump sum	rupees		25
2	Dismantling and removing masonry walls	Lump sum	rupees		5
3	Earthwork excavation	Grade	0 4 0	29·68	742
4	Earthwork to flank bund excavated earth of approach and draft clearing got from left waste weir	,,	0 1 0	200	13
5	Diversion of cart track	Lump sum	rupees		25
6	Concrete in surki mortar	C.ft.	0 4 6	990	275
7	Burnt brick in surki mortar	,,	0 6 0	36·02	1,351
8	Rebuilding the damaged masonry and resetting the slab.	Lump sum	rupees		25
9	Burnt stone slabs 6" thick dressed and fixed with surki mortar pointing.	S.ft.	1 0 0	994	994
10	Plastering with surki mortar	Sqr.	5 0 0	35·45	177
11	Rough stone work new with large stones 5 to 6 miles lead.	Grade	3 0 0	515	1,545
12	Unforeseen items during execution of work	Lump sum	rupees		43
13	Compensation for dry lands	Acres	100 0 0	3	300
	Total for left weir				5,520
	IV. RIGHT WEIR 80' LONG AT R. L. 50·00.				
1	Jungle clearing	Lump sum	rupees		5
2	Excavating soft stuff and white stoney	Grade	1 0 0	107	107
3	Benching block broken trap	,,	10 0 0	41	410
4	Cement concrete for levelling up foundation	Lump sum	rupees		50
5	Split rough stone in surki mortar	C.ft.	0 6 0	10·102	3,788
6	Removing and refixing slab set in surki mortar (7½" thick old).	S.ft.	0 4 0	479	119
7	Making holes to orifice guide and coping slab	Each	2 0 0	4	8
8	Cement pointing	Sqr.	4 8 0	38·06	171
9	Providing and fixing wooden plug with iron rod, lock and key, complete.	Each	50 0 0	1	50
10	Earthwork to flank bund	Grade	0 4 0	817	204
11	Rough stone work, new	C.yd.	3 0 0	22	66
12	Unforeseen item during execution of work	Lump sum	rupees		21
	Total for right weir				4,999
	V. LIFTING DAM.				
1	Dismantling the existing masonry lifting dam and repairing the junction with necessary bond stones.	Lump sum	rupees		50
2	Benching harder white rock	C.yds.	10 0 0	21	210
3	Excavating soft white rock	,,	1 0 0	104	104
4	Cement concrete for levelling up foundations	Lump sum	rupees		50
5	Split stone in surki mortar (with old and available at site).	C.ft.	0 6 0	4,008	1,503
6	Removing and refixing slab set in mortar (7½" thick).	S.ft.	0 4 0	330	82
7	Cement pointing	Sqr.	4 8 0	17·72	80
8	Rough stone work, new	C.yds.	3 0 0	175	525
9	Repairing the skin walls	Lump sum	rupees		50
10	Unforeseen items during execution	Lump sum	rupees		52
	Total for lifting dam				2,706

L. A. H. WINCHLER,
Executive Engineer.
6 G